

Notice of Authorization

Permit Number 11-47-0091-P

Issued: 12/11/2012 Expiration Date: 12/11/2017

The Michigan Department of Environmental Quality, Water Resources Division, P.O. Box 30458, Lansing, Michigan 48909-7958, under provisions of the Natural Resources and Environmental Protection Act, 1994 PA 451, as amended, and specifically:

Part 31, Floodplain Regulatory Authority of the Water Resources Protection.

Part 301, Inland Lakes and Streams.

Authorized activity:

Install turbidity curtain and silt fence around the island perimeter.

Temporarily remove the existing pre-cast concrete stair case and re-install upon seawall completion.

Temporarily remove 11 cubic yards of existing broken concrete riprap from below the legal lake level of 894.0 to provide a 2-foot wide open corridor in which to install a new 300 foot long steel or vinyl seawall.

Replace the 11 cubic yards of broken concrete on the waterward side of the wall.

Place 20 cubic yards of 8-inch to 12-inch diameter natural stone at the toe of the 300 foot seawall.

Place 12 cubic yards of backfill in the landward side of the seawall.

Construct a 6 foot wide by 60 foot long dock.

All construction shall be completed in accordance to the attached plans and conditions.

To be conducted at property located in: Livingston County, Waterbody: Runyan Lake Section 9, Town 4N, Range 6E, Tyrone Township.

Permittee:

Runyan Lake Inc. P O Box 105 Fenton, MI 48430

Carol Valor

Water Resources Division

517-373-7055

This notice must be displayed at the site of work.

Laminating this notice or utilizing sheet protectors is recommended.

Please refer to the above Permit Number with any guestions or concerns.